

ACTIVITY

AMOUNT

Construct 30'x80'x12' engineered weld-up stand-alone metal building on slab 4" deep with 3/8" rebar on 12" centers; color choice to be determined; 2 - 3' swing-out doors will be installed. Building will be insulated with 1" close cell insulation. Bid includes electrical, plumbing and HVAC with 2 5-ton units with duct work. Flooring will be vinyl plank; Mechanical closet, coaches' office, shower and both restrooms will have dropped ceiling. Other area will have open ceiling. Shower will have ceramic tile and floor; All other interior walls will be constructed of 8' R panel, color of choice to be determined. Both restrooms will be ADA approved. There will be 7 - 3070 metal doors.

380,000.00

Existing building and concrete in location will be removed.

Because the survey has not come back yet, this bid does not include any dirt or dirt work for the pad. There will be additional charge if that is required.

Estimate submitted by:
L&L Construction
806-893-7628

TOTAL

\$380,000.00

Accepted By

Accepted Date