



Quote Number: 3ES07MAY26

To: Galveston ISD (Buy Board 757-24)

Attention: James

Project: Perimeter & Playground Fence - Rev 3

Date: 11-Jun-2026

Foster Fence will provide and install the following:

-West Perimeter Fence

- Demo 615 linear feet of existing chain link fence. (pull post)
- Install 1,867 linear feet of 8' black vinyl chain link fence w/2" x 8ga fabric (Extruded), 1 5/8" schedule 40 top rail, 2 3/8" schedule 40 line post spaced 10' on center, 3" schedule 40 terminal post, and brace/truss at ends, pulls, corners, and gates.
- Install (1) 4' wide black vinyl chain link panic gate w/post framed header, key override w/construction core, hydraulic closer, and panic hardware.
- Install (1) 4' wide black vinyl chain link single swing gate w/post and standard hardware.
- Install (2) 8' wide black vinyl chain link double swing gate w/post and standard hardware.

Playground Fence

- Demo 216 linear feet of existing chain link fence. (pull post)
- Demo (1) 3' single swing gate.
- Demo (1) 6' wide double swing gate.
- Install 325 linear feet of 8' black vinyl chain link fence w/2" x 8ga fabric (Extruded), (2) 1 5/8" schedule 40 top and bottom rails, 2 3/8" schedule 40 line post spaced 10' on center, 3" schedule 40 terminal post, and brace/truss at ends, pulls, corners, and gates.
- Install (1) 4' wide black vinyl chain link panic gate w/post framed header, key override w/construction core, hydraulic closer, and panic hardware.
- Install (2) 6' wide black vinyl chain link double swing gate w/post and standard hardware.
- All fence framework and gates will be powder coated black.
- No written fence specifications or detailed drawings were provided.
- Post on concrete will be anchor bolted to concrete.
- Excludes 911 provisions, permits, electrical, access controls, mow band and fence grounding.
- Mobilization to and from the job site, supervision, and management required for complete installation.

Total **\$183,555.00** Tax not included

Estimated Taxes \$0.00 *If applicable

*Quote is good for 30 days

Elbert Salas - esalas@fosterfence.com - 713-851-1098

*Lead times are projected after submittals are approved

(281) 456-7273

(281) 456-0221 Fax

FOSTER FENCE LTD

P.O. Box 96116
Houston, TX 77213

www.fosterfence.com

info@fosterfence.com



Standard Exclusions- unless specifically included in the quote:

- Work to be performed during standard business hours, 7am-5pm Monday through Friday. Any work that needs to be performed after hours or on the weekend will come at an added cost and will need to be quoted accordingly.
- Demolition, clearing & grubbing, spoil removal.
- Electrical work, access controls, and conduits.
- Fence and controls grounding.
- Engineered drawings and Building Information Modeling (BIM).
- Fence of fire department permitting.
- Property surveying and site layout. The final location of the fence installation is to be verified with the customer/agent and Foster Fence staff before starting the installation.
- Tree protection, silt fence, temporary fence.
- Hand digging, hydro-excavation, core drilling, rock drilling, and probing.
- Concrete & asphalt breaks.
- Signage, bollards, concrete mow strip.
- Painting, staining and galvanizing after fabrication.
- Utility locates beyond 811 One call, location of water lines. Private utility lines are not covered by 811. Locating private lines is the responsibility of the property owner.
- OQ training, OSHA 30 Training, site, or hazard-specific training greater than 30 minutes.
- Re-mobilizations, downtime, standby time.
- OCIP, CCIP, Builders Risk, Payment, and Performance Bonds.
- In order to keep your fence and gates in safe working order, customers are strongly advised to follow the maintenance guidelines provided on our website, visit fosterfence.com/resources for more detailed information.

Commercial Conditions:

- All projects requiring special fabrication as well as contracts with a value greater than \$75,000 will require signed and approved submittals before Foster Fence, Ltd. proceeds with construction.
- Lead times are projected after submittals are approved.
- Terms – Net 30, unless otherwise expressly negotiated.
- All standby/downtime of more than 30 minutes will be billed at a rate of \$400 per hour.
- Restocking fee for standard stock materials 25%, non-stock materials 100%.
- Foster Fence Ltd. agrees to guarantee all materials are free from defects in materials and workmanship. for a period of one year from installation. This guarantee does not cover abuse, Acts of God, nature, or other external sources.

Customer Signature

Date

(281) 456-7273
(281) 456-0221 Fax

FOSTER FENCE LTD
P.O. Box 96116
Houston, TX 77213

www.fosterfence.com
info@fosterfence.com