



**COUNTRY NURSERY, INC.**  
 85603 579TH AVE  
 WAYNE, NE 68787  
 PHONE: 402-375-4643

# PROPOSAL

EMERSON ELEMENTARY  
 SCHOOL  
 EMERSON, NE  
 ATTN: DUSTIN NIELSEN

Date	Proposal #
1/26/2026	13348
Phone Number	

Project:	PLAYGROUND AREA
----------	-----------------

Qty	Description	Size	Cost Ea.	Total
3	Removal/Disposal of existing PLAYGROUND EQUIPEMNT AND GRAVEL with necessary workers ( 3) and equipment (Pro-Rated). = WE DISPOSE OF GRAVEL IN EMERSON.	CREW DAY	1,880.00	5,640.00T
1	DISPOSAL FEE - if we have to haul out of Emerson - will bill on actual *****IF Removals ARE we done by School employees - we will take off 1/2 day of removal charges. **** NOTE DISPOSAL AND REMOVAL CHARGES ARE PRO-RATED = YOU WILL ONLY GET CHARED THE HOURS THAT IT TAKES US.		0.00	0.00
30	TOPSOIL - AS NEEDED - WILL BILL ON ACTUAL USED.	Ton	50.00	1,500.00T
1	ROUGH AND FINAL GRADING (includes necessary equipment and 2-3 workers on site to prepare land for seeding or sodding). Working of soils on site to create smooth, free draining and even surface with a loose, moderately coarse texture. Ridges removed and fill depressions as required for drainage.	CREW DAY	1,880.00	1,880.00T
1	CLAUSSEN & SONS IRRIGATION: includes everything needed to install and operate the irrigation system EXCEPT: DOES NOT INCLUDE: suppling water to the outside of the building. A plumber will need to get a 1" water line outside of the building. ALSO DOES NOT INCLUDE: electrical if needed to be added to the outside of the building.	LS	5,223.75	5,223.75T

**Subtotal**

**Sales Tax (0.0%)**

**Total**

 <p>Like us on FaceBook!          Check us out on <a href="http://www.countrynursery.net">www.countrynursery.net</a></p>
-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------



**COUNTRY NURSERY, INC.**  
 85603 579TH AVE  
 WAYNE, NE 68787  
 PHONE: 402-375-4643

# PROPOSAL

EMERSON ELEMENTARY  
 SCHOOL  
 EMERSON, NE  
 ATTN: DUSTIN NIELSEN

Date	Proposal #
1/26/2026	13348
Phone Number	

Project:	PLAYGROUND AREA
----------	-----------------

Qty	Description	Size	Cost Ea.	Total
1	JORGENSEN CONCRETE AND CONSTRUCTION: labor and materials to complete the following in the playground area. Dig out, form up, install rebar, and pour new concrete in the following areas: ***** all concrete areas include: concrete and rebar 2' on center pinned into existing concrete 75X10 sidewalk from double gates to existing concrete in the middle of school on north end. 50X4 sidewalk from existing sidewalk on northwest corner of school to existing concrete in middle of school on north end. 75X10 sidewalk to concrete drainage swale. tear out of existing section of damage concrete at the top of the drainage swale and install rebar and pour concrete in same area.		14,987.50	14,987.50T
817	TURF TYPE FESCUE SOD; Includes sod, installation. 7353sq' = 817 yds	ROLL	5.50	4,493.50T
78	TURF TYPE FESCUE SOD; Includes sod, installation. 700sq' - NORTH SIDE	ROLL	5.50	429.00T
134	TURF TYPE FESCUE SOD; Includes sod, installation. 1500sq' - SOUTH SIDE	ROLL	5.50	737.00T
1	CLAUSSEN & SONS IRRIGATION : ADDITIONAL AREAS	LS	775.00	775.00T
1	ELLIS PLUMBING : LANDSCAPE MAINTENANCE	LS	600.00	600.00T
1	CASEY ELECTRIC : LANDSCAPE MAINTENANCE	LS	500.00	500.00T

COUNTRY NURSERY LIMITED WARRANTY  
 (Only When Country Nursery Installs)  
 Trees-One Year, Shrubs-Sixty Days, Roses & Perennials-Hold No Guarantee. Labor charges to replant not included.

**Subtotal** **\$36,765.75**  
**Sales Tax (0.0%)** \$0.00  
**Total** **\$36,765.75**



Like us on FaceBook!  
 Check us out on [www.countrynursery.net](http://www.countrynursery.net)