



Quote: 25577

Rev: 1

Date: 4/24/2026

Quote valid for 90 days

Project: EXISTING ALEDO MIDDLE SCHOOL RENOVATION AND ADDITION

City: Aledo

State: TX

Company: Huckabee

Location:

Name: Joshua Cogburn

Email: Joshua.Cogburn@huckabee-inc.com

Phone: 0

**Business Development Manager**



Chris Childress



972 353 8482 x 52



469 500 4164



cchildress@vivarailings.com



vivarailings.com

**Inside Sales Specialist**



Paul Legaspi



972 353 8482 x 56



plegaspi@vivarailings.com



vivarailings.com



151 W. Vista Ridge Mall Dr. Lewisville, TX 75067



info@vivarailings.com



972.353.8482

Quote: 25577                                      Rev: 1                                      Date: 4/24/2026                                      Spec: VIVA AS ALT

PROJECT NAME: EXISTING ALEDO MIDDLE SCHOOL RENOVATION AND ADDITION                                      EST: BT

REVISION

	Date	Description
REVO	2/17/2025	Replacing Multiline infill
REV1	4/24/2026	Price Updated per Customer Request Based on REVO Scope Amount

SUMMARY

	Quantity	Unit	RAILING SYSTEM TYPE		COST
SYSTEM 1	231	LF	CUBE MULTILINE	MATERIAL	\$ 21,617
				INSTALL	\$ 37,897
SYSTEM 2	24	LF	CUBE MULTILINE	MATERIAL	\$ 3,793
				INSTALL	\$ 4,180
<b>GRAND TOTAL</b>					<b>\$ 67,486</b>



vivarailings.com



151 W. Vista Ridge Mall Dr. Lewisville, TX 75067



info@vivarailings.com



972.353.8482



SYSTEM 1

CUBE MULTILINE Guardrail HT: Mounting condition: top mount & welded

In-fill: 1/2" Ø TUBING MULTILINE RAIL

Item	Description:	Reference	Qty (Ln Ft)
1	Cafetorium Area - Level Guardrail	E02,	171
2	Cafetorium Area - Rake Guardrail	E02,	60
			231

Note:

1. This quote includes only replacing multiline infill at the existing railings in the Cafeteria area. **1/2" tube infills will be replaced with 1/2" round bars**, to be installed in the **bottom five rows** where indicated in the shop drawings.
2. Quote excludes removal of multiline holders on existing Cube post.
3. This quote includes the new Corner Cage design, as shown in the shop drawings, with a total quantity of two (2).
4. All multi-line fittings and mechanical connections in this area shall be tack welded.

Furnish Materials for system 1 as above: \$ 21,617  
*Sales tax excluded*

Install system 1 as above: \$ 37,897



SYSTEM 2

CUBE MULTILINE Mock-up Mounting condition: top mount & welded

In-fill: 1/2" Ø TUBING MULTILINE RAIL

Item	Description:	Reference	Qty (Ln Ft)
1	Cafetorium Area - Level Guardrail	E02,	24
			24

Note:

See notes above

Furnish Materials for system 2 as above: \$ 3,793  
*Sales tax excluded*

Install system 2 as above: \$ 4,180



**TOTAL (excludes any alternates) Furnish and Install** **\$ 67,486**

\*\*This quote is subject to adjustment in the event of future tariff actions, material cost escalations, or other significant changes in market conditions

\*As scale of economies for complete project scope is taken into account, re-pricing will be required if only a portion of the scope is purchased. Individual breakout pricing is for accounting purposes only and is not valid for a PO or contract.

Provide Performance and Payment Bond (1.65%) ADD \$ 1,114

All bonds are 1 year - award to completion. Additional years will require rate adjustment

Professional Liability Insurance (3M Occurance/ Aggregate) ADD \$ 1,500

**Note:**

Quote is valid only for materials and quantities stated above. Any support steel or modifications to structure required for installation are BY OTHERS and are EXCLUDED.



vivarailings.com



151 W. Vista Ridge Mall Dr. Lewisville, TX 75067



info@vivarailings.com



972.353.8482

<b>Shop Drawing Lead Time:</b> TBD at the time of order placement	TBD
<b>Material Lead Time-</b> from approved submittals and Field dimensions/ hold-to dimensions	14-16 Weeks
**Custom fab time may vary - Shorter lead times available on request	
<b>Field Measurement Trip</b> (with install alternate only)*	1
**VIVA Recommends "hold-to" dimensions to facilitate schedule compression	
<b>Install Mobilizations Included</b> (with install alternate only)*	1
**Additional trips pricing at request	

<b>STANDARD ALTERNATES (Not Included in Base Bid):</b>	<b>COST</b>
Base Structure CAD Service (reqd. in absence of stair fabricator dwgs in .dwg/.dxf)	<b>\$1500 / Floor</b>
Additional drawing revisions due to change of design, structure or provided field measurements (Base Bid include 1 Revision)	<b>\$2500 / Rev</b>
Billing service fee (Textura)	<b>0.25% of contract amount</b>
Additional Mobilization cost	<b>\$ 2,500 Ea</b>

**Payment Terms:**

- Material Furnish only: Contract Value < \$50,000 - 50% Advance and balance on material ready and before shipping.
- Material Furnish only: Contract Value < \$100,000 - 25% Advance + 25% on approved Shop Drawings and balance on material ready and before shipping.
- Material Furnish only: Contract Value >\$100,000 - 15% Advance + 40% on approved Shop Drawings and balance on material ready and before shipping.
- Furnish & Install: Progress billing per established schedule of values.
- Buy America Proposals valid for 90 day only. 25% Material payment due at time of award/ release.

**MATERIAL INCLUSIONS/EXCLUSIONS**

- YES Furnish material as above
- YES Shop Drawings
- YES Shipping
- YES 1 Year Warranty (1 year standard manufactures warranty included)
- YES GL Insurance
- YES Provide PE Stamped Submittal
- YES Standard #6 Satin Brushed Stainless Steel Finish
- YES Installation
- NO Mockup (ADD \$2750 for Single Panel Mockup or \$1500 for 12"x18" Table Top Mockup (materials only))
- NO Sales Tax
- NO Professional Liability Insurance.
- NO Mounting Anchors (Included with Installation Alternate)
- NO SS-316 alloy (standard stainless steel alloy 304 is included) reference system description for details
- NO Buy America/n raw material supply requirement
- NO SS Directional finish.
- NO Embeds

- NO Any railing scope beyond listed above
- NO Any supporting structural steel (adequate support steel required per engineering)
- NO Temporary Railing
- NO Temporary protection or protection of installed material
- NO Caulking or Silicone Sealant
- NO Cladding or break metal
- NO Coring
- NO Fire watch
- NO Billing services fees (Textura etc)
- NO OCIP/CCIP Project
- NO Payment and Performance Bond
- NO Developing stair or structure CAD drawings or converting from paper to CAD
- NO Painting or wood staining (any wood provided is unstained)
- NO Deviation from approved shop drawings
- NO Time or cost impact due to changes in structure or site conditions from approved shop drawings
- NO Indemnification for "gross" or "sole" negligence
- NO Project specific testing if Specifications call out for Product Test Reports (per industry standard this requirement is typically sufficed via Engineering calculations and PE stamped drawings)
- NO Bent Glass (UON) with limited radius set-ups as indicated above, any additional set-ups would be at extra cost
- NO Structural Steel tolerances (deviations) of beyond 1/8" over 10' in long direction (camber & sweep); and 1/8" in the vertical direction along the cross section.  
 Concrete slab tolerances (deviations) of beyond 1/4" over 10' in direction.

**INSTALL INCLUSIONS - APPLICABLE ONLY WHEN INSTALL ALTERNATE IS PURCHASED**

- YES Field Measurements
- YES Hoisting equipment and crane time
- YES Installation Tools, Equipment, Swaging Machine, injection guns or dispensers
- YES WC Insurance
- NO Re-install or any additional work due to waterproofing requirements or any other trade needs
- NO Union Labor
- YES Prevailing Wage

[To view our qualifications, terms, and conditions, please click here or scan the QR code provided.](#)



Respectfully submitted,  
 VIVA Railings, LLC  
 If acceptable, please sign and return. Thank you for choosing VIVA Railings!

Signature: \_\_\_\_\_ Name: \_\_\_\_\_  
 Company: \_\_\_\_\_