

Quote

Century Fence Company
14839 Lake Dr NE
Forest Lake, MN 55025



Quote To:

Derrick Retz
BOYCEVILLE SCHOOL DISTRICT
1003 Tiffany Street
Boyceville, WI 54725

Project Location:

Tiffany Creek Playground Fence Addition

Quote #: 35857

Quote Date: 4/21/2026

Description

Furnish and install 300 LF of 4 Foot high galvanized chain link fence. Line posts shall be 2" O.D. Galvanized steel pipe Driven 48" in depth and spaced a maximum of 10' on centers. The fence shall consist of top rails which will be 1-5/8" O.D. Galvanized pipe. The fence shall consist of bottom tension wire.

- 2 - End post: 2-1/2" O.D. Galvanized pipe - Driven
- 2 - Corner post: 2-1/2" O.D. Galvanized pipe - Driven
- 4 - Gate post: 3" O.D. Galvanized pipe - Concrete Set
- 1 - Single Swing Galvanized Gate: 6' Opening Width
- 1 - Double Swing Galvanized Gate: 12' Opening Width

Notes:

Excludes Asphalt patching, Clearing, Excavation through rock, Excavation through frost, Hydro-excavating, Permit, Private Utility Locate

Quote Total: \$8,700.00

Quote Valid For 15 days

Buyer's Signature: _____

Date: _____

Submitted by:

Jason Larson

Change Acceptance:

This quote when accepted in writing by purchaser and by Century Fence Company includes the terms and conditions set forth on www.centuryfence.com which are incorporated by reference and becomes a contract between two parties. If the project is cancelled upon agreement and special materials were purchased, the customer agrees to pay 100% of the material cost

Jason Larson

Office: 651-464-7373

Cell: 612-666-1680

Email: JLarson@centuryfence.com

Terms of Payment: Net Cash upon receipt of invoice.